



RANG DESIGN STUDIO (SA0590190-H)

1C, Jalan Desa Jaya, Taman Desa, 58100, KL.

03- 7972 6609

rangdesignstudiomy@gmail.com

QUOTATION

Prepared By : Quinn  
Reference : # RDS-1123-057-R4  
Date issued: 29 Mar 2024

|                                                                 |                    |
|-----------------------------------------------------------------|--------------------|
| ATTN : Jebsen & Jessen Packaging Sdn. Bhd.   017- 727 4535_Emma | Size : 6350 SQ.FT. |
| Project : Jebsen & Jessen Packaging Sdn. Bhd. @ Sungai Buloh    | Type : -           |

| # | ITEMS DESCRIPTION                                                                     |                                                                                                  | AREA      | QTY. | UNIT   | RATE | TOTAL |
|---|---------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------|-----------|------|--------|------|-------|
|   |                                                                                       |                                                                                                  |           |      |        | RM   | RM    |
| 1 | Preliminary Work                                                                      |                                                                                                  |           |      |        |      |       |
| a | Standard Roro Bin                                                                     | To supply manpower & roro bin for all debris & waste disposal on site.                           |           | 3    | UNIT   | 240  | 720   |
| b | Standard Protection & Cleaning                                                        | To supply manpower, materials & tools to lay blue white canvas protection. ( Door & Glass only ) |           | 1    | L.S    | 1000 | 1,000 |
| c | Demolish of existing plaster ceiling and partition.                                   |                                                                                                  |           | 1    | L.S    | 3000 | 3,000 |
| 2 | Mechanical & Electrical Work                                                          |                                                                                                  |           |      |        |      |       |
| a | Light Point                                                                           | To supply manpower, materials & tools to loop new lighting point.                                |           | 160  | UNIT   | 85   | 13600 |
| b | Power Point                                                                           | To supply manpower, materials & tools to loop new 13A plug point.                                |           | 7    | UNIT   | 100  | 700   |
| c | Led Strip light                                                                       | To supply manpower, materials & tools to install LED strip w/ driver.                            | Lobby     | 4    | UNIT   | 250  | 1000  |
| d | Downlight                                                                             | To supply & install.                                                                             |           | 152  | UNIT   | 50   | 7600  |
| e | Track Light                                                                           | To supply & install.                                                                             | Lobby     | 1    | UNIT   | 200  | FOC   |
| f | Pendant Light                                                                         | To install.                                                                                      |           | 5    | UNIT   | 80   | 400   |
|   | * Installation (Inst.) work above are not including supply of fixture, unless stated. |                                                                                                  |           |      |        |      |       |
| 3 | Wet Work                                                                              |                                                                                                  |           |      |        |      | N/A   |
| 4 | Ceiling Work                                                                          |                                                                                                  |           |      |        |      |       |
| a | Plaster Ceiling                                                                       | To supply manpower, materials & tools to install 9mm thk. plaster ceiling,                       |           | 6350 | SQ.FT. | 4.2  | 26670 |
| 5 | Painting / Wallpaper                                                                  |                                                                                                  |           |      |        |      |       |
| a | Interior Wall                                                                         | To supply manpower, materials & tools to paint interior wall. * 2 coats                          |           | 6350 | SQ.FT. | 2    | 12700 |
| b | Ceiling                                                                               | To supply manpower, materials & tools to paint interior ceiling. * 2 coats                       |           | 6350 | SQ.FT. | 0.9  | 5715  |
| 6 | Partition, Door, Window, and Panelling Work                                           |                                                                                                  |           |      |        |      |       |
| a | Partition Wall                                                                        | To supply manpower, materials & tools to construct wall w/ 9mm Thk. gypsum.                      |           |      |        |      |       |
|   | 27000mm x 2400mm                                                                      |                                                                                                  | Extension | 800  | SQ.FT. | 12   | 9600  |
|   | 2100mm x 1500mm                                                                       |                                                                                                  | Auto      | 35   | SQ.FT. | 12   | 420   |
|   | 5100mm x 2700mm                                                                       |                                                                                                  | COO/CM    | 153  | SQ.FT. | 12   | 1836  |
|   | 1200mm x 1800mm x 2Unit                                                               |                                                                                                  | Phone B.  | 48   | SQ.FT. | 12   | 576   |
| b | Door                                                                                  | To supply manpower, materials & tools to install.                                                |           |      |        |      |       |

|    |                       |                                                                                                                                                                                        |                          |                 |                            |                |                      |
|----|-----------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------|-----------------|----------------------------|----------------|----------------------|
|    |                       | File Room, Big & Small Meeting                                                                                                                                                         |                          | 3               | UNIT                       | 800            | 2400                 |
|    |                       | COO Room, CM Room                                                                                                                                                                      |                          | 2               | UNIT                       | 800            | 1600                 |
| c  | Glass Wall            | To supply manpower, materials & tools to construct.<br>5400 mm x 2400mm<br>2100mm x 2400mm<br>2700mm x 2400mm                                                                          | B. Meet<br>S. Meet<br>CM | 144<br>56<br>72 | SQ.FT.<br>SQ.FT.<br>SQ.FT. | 45<br>45<br>45 | 6480<br>2520<br>3240 |
| d  | Glass Door            | To supply manpower, materials & tools to install.<br><i>Material : 10mm Thk Tempered Clear Glass</i><br><i>Dimension : W 800mm x H 2100mm</i>                                          | Phone B.                 | 2               | UNIT                       | 1400           | 2800                 |
| e  | Tinted                | To supply manpower, materials & tools to install.                                                                                                                                      |                          | 320             | SQ.FT.                     | 5800           | FOC                  |
| 7  | Carpentry Work        |                                                                                                                                                                                        |                          |                 |                            |                |                      |
| a  | Wall Cabinet          | To supply manpower, materials & tools to install.<br><i>Material : Melamine</i><br><i>Dimension : W 900mm x D 400mm x H 1200mm</i>                                                     | Lobby                    | 3               | FR.                        | 300            | 900                  |
| a1 | Glass Door            |                                                                                                                                                                                        |                          | 1               | L.S.                       | 900            | 900                  |
| b  | Wall Panel            | To supply manpower, materials & tools to install.<br><i>Material : Melamine</i><br><i>Dimension : W 3000mm x D 1200mm x FH</i>                                                         |                          | 1               | L.S.                       | 1800           | FOC                  |
| c  | Storage Cabinet       | To supply manpower, materials & tools to install.<br><i>Material : Melamine</i><br><i>Dimension : W 3000mm x D 400mm x FH</i>                                                          | CS                       | 10              | FR.                        | 520            | 5200                 |
| d  | Base Cabinet          | To supply manpower, materials & tools to install.<br><i>Material : Melamine</i><br><i>Dimension : W 1800mm x D 400mm x H 850mm</i>                                                     | CS                       | 6               | FR.                        | 350            | 2100                 |
| e  | Base Cabinet          | To supply manpower, materials & tools to install.<br><i>Material : Melamine</i><br><i>Dimension : W 2400mm x D 400mm x H 850mm</i>                                                     | Auto-<br>mation          | 6               | FR.                        | 350            | 2100                 |
| f  | Storage Cabinet       | To supply manpower, materials & tools to install.<br><i>Material : Melamine</i><br><i>Dimension : W 3300mm x D 400mm x FH</i>                                                          | Auto-<br>mation          | 11              | FR.                        | 520            | 5720                 |
| g  | Reception Counter     | To supply manpower, materials & tools to install.<br><i>Material : Plywood</i><br><i>Dimension : W 4500mm x D 600mm x H 1000mm</i>                                                     | CS                       | 1               | L.S                        | 13000          | 13000                |
| h  | Bench Seat            | To supply manpower, materials & tools to install.<br><i>Material : Plywood</i><br><i>Dimension : W 4800mm x D 450mm x H 50mm (w/o storage)</i>                                         |                          | 16              | FR.                        | 300            | 4800                 |
| h  | Base Cabinet          | To supply manpower, materials & tools to install.<br><i>Material : Melamine</i><br><i>Dimension : W 4900mm x D 400mm x H 850mm</i>                                                     | CEO<br>Room              | 17              | FR.                        | 300            | 5100                 |
| 8  | Flooring              |                                                                                                                                                                                        |                          |                 |                            |                |                      |
| a  | Vinyl Flooring        | To supply manpower, materials & tools to install 3mm thk. Vinyl Flooring.<br>* inc skirting, dismantle and dispose of existing carpet, w/o self leveling.                              |                          | 5950            | SQ.FT.                     | 7.5            | 44625                |
| 9  | Proffesional Services |                                                                                                                                                                                        |                          |                 |                            |                |                      |
| a  | Design Consultation   | * Space Planning<br>* Design Consultation<br>( Aesthetic, Function, Lighting / Material & Loose Furnishings Selection )<br>* 3D Visualization<br>* Construction Drawing / 2D Detailing |                          | 1               | L.S.                       | 3000           | 3000                 |
| 10 | Loose Furniture       |                                                                                                                                                                                        |                          |                 |                            |                |                      |
|    | 1 Table               | To supply & Install.                                                                                                                                                                   |                          | 3               | UNIT                       | 190            | 570                  |

|                                |                                   |                      |    |      |      |      |
|--------------------------------|-----------------------------------|----------------------|----|------|------|------|
|                                | Dia. 800mm / Black                | Reception & Showroom | 5  | UNIT | 150  | 375  |
| 2 Chair                        | To supply & Install.              |                      | 12 | UNIT | 250  | 3000 |
|                                | Dark Blue x2, Dark Orange x2      |                      |    |      |      |      |
| 3 Metal Display Shelf          | 2000 x 120 x 300mm w/ LED strip   |                      | 2  | UNIT | 490  | 980  |
| 4 Picture Frame                | A4 Size / Walnut Colour           |                      | 12 | UNIT | 30   | 360  |
| 5 Wording _ JNJP               | Silver 10 x 6,6 cm                | Reception            | 1  | L.S. | 154  | 154  |
| 6 Wording _ JNJG               | Silver 10 x 6,6 cm                |                      | 1  | L.S. | 140  | 140  |
| 7 Pendant Light                | 1200mm / White Frame / Warm Light |                      | 2  | UNIT | 175  | 350  |
| 8 Artificial Pot Plant         | 1600mm Height                     |                      | 1  | UNIT | 168  | 168  |
| 9 Wording _ JNJPSB             |                                   |                      | 1  | L.S. | 196  | 196  |
| 10 Wording _ CS                |                                   | CS                   | 1  | L.S. | 105  | 105  |
| 11 Artificial Plant            | 650 x 200mm                       |                      | 1  | UNIT | 75   | 75   |
| 12 Planter Pot                 | 700 x 300 x 300mm                 |                      | 1  | UNIT | 150  | 150  |
| 13 Office Table                | 5600mm x 1200mm _ 8 Pax           |                      | 3  | UNIT | 3050 | 9150 |
|                                | 4200mm x 1200mm _6 Pax            |                      | 1  | UNIT | 2400 | 2400 |
| 14 Office Chair                | Grey                              | Open Office          | 33 | UNIT | 180  | 5940 |
| 15 Planter Storage             | White 1200 x 300 x 800mm          |                      | 5  | UNIT | 460  | 2300 |
| 16 Pot Plant                   | To supply.                        |                      | 5  | UNIT | 600  | FOC  |
| 17 CEO Table                   | 2200mm c/w build in power point   |                      | 1  | UNIT | 2500 | 2500 |
| 18 CEO Chair                   | Orange / Cream White              |                      | 1  | UNIT | 475  | 475  |
| 19 Chair                       | Cream White / Muted Orange        |                      | 2  | UNIT | 330  | 660  |
| 20 Artificial Plant            | 1600mm Height                     |                      | 1  | UNIT | 168  | 168  |
| 21 Sofa                        | 2200mm                            | CEO Room             | 1  | UNIT | 3380 | 3380 |
| 22 Coffee Table                | Dia. 450mm                        |                      | 1  | UNIT | 240  | 240  |
| 23 Venetian Blind              | Matte Black                       |                      |    |      |      |      |
|                                | W 2700mm x H 2100mm               |                      | 1  | UNIT | 400  | 400  |
|                                | W 4200mm x H 2100mm               |                      | 1  | UNIT | 630  | 630  |
| 24 White Board ( White Glass ) | 5ft x 3 ft                        |                      | 1  | UNIT | 700  | 700  |
| 25 Pendant Light               | 1200mm Tunable Light              | CEO / CM / COO       | 3  | UNIT | 220  | 660  |
| 26 Table                       | Dia. 600mm                        |                      | 2  | UNIT | 298  | 596  |
| 27 Chair                       | Dark Blue                         |                      | 4  | UNIT | 250  | 1000 |
| 28 Venetian Blind              | Matte Black                       | CM / COO Room        |    |      |      |      |
|                                | W 2600mm x H 2100mm               |                      | 2  | UNIT | 330  | 660  |
| 29 White Board ( White Glass ) | 5ft x 3 ft                        |                      | 2  | UNIT | 700  | 1400 |
| 30 Meeting Table_ 12 Pax       | 4800mm x 1500mm                   |                      | 1  | UNIT | 4800 | 4800 |
| 31 Meeting Chair               | Grey                              |                      | 12 | UNIT | 365  | 4380 |
| 32 Side Table                  | Glossy Black / Dia. 400mm         | Meeting (Big)        | 3  | UNIT | 140  | 420  |
| 33 Bench Cushion               | 2400mm x 400mm                    |                      | 2  | UNIT | 290  | 580  |
| 34 White Board                 | 6ft x 4 ft                        |                      | 2  | UNIT | 1180 | 2360 |
| 35 Meeting Table _ 6 Pax       | Cream White                       |                      | 1  | UNIT | 2150 | 2150 |
| 36 Meeting Chair               | Dark Walnut / Orange              | Meeting (Small)      | 6  | UNIT | 365  | 2190 |
| 37 White Board                 | 6ft x 4 ft                        |                      | 1  | UNIT | 1180 | 1180 |
| 38 Vertical Blind              | White ( Semi Transparent )        |                      |    |      |      |      |
|                                | W 5400mm x H 2700mm               | Meeting Room         | 1  | UNIT | 398  | 398  |
|                                | W 2100mm x H 2700mm               |                      | 1  | UNIT | 160  | 160  |

|               |                                                |  |  |  |                     |         |
|---------------|------------------------------------------------|--|--|--|---------------------|---------|
|               |                                                |  |  |  | Sub Total           | 250,147 |
| PAYMENT TERMS |                                                |  |  |  |                     |         |
| 35 %          | Deposit                                        |  |  |  | Deposit Paid        | -8000   |
| 35 %          | Progress Claim                                 |  |  |  |                     |         |
| 20 %          | Completion of all contract scope               |  |  |  | Round Up Adjustment | -147    |
| 10 %          | Retention for defect rectification ( 30 days ) |  |  |  |                     |         |
|               |                                                |  |  |  | TOTAL               | 242,000 |

BY THIS CONSENT, I / WE UNDERSTAND AND AGREED THAT :

- 1 Any alteration on above stated quotes shall be considered as variation order.
- 2 Additional charges shall be applied if extra works that are not stated in above quotation is required.
- 3 Client shall be responsible for the results of any changes after the work has commenced, such as delay of schedule, quality of outcome and etc.
- 4 Client shall still pay RANG DESIGN STUDIO full prices as stated in this quotation, regardless of any cancellation after the work has commenced.
- 5 Price as quote shall base on supplier schedule availability, rush project might subject to price changes as we needs to work with alternative supplier.
- 6 All item quoted are based on RANG DESIGN STUDIO moderate standard, additional charges shall be applied if there's any upgrade on items.
- 7 Deposit paid are non-refundable.
- 8 Goods sold are non-exchangeable and non-returnable.
- 9 Any cost needed for permit, approvals or certification shall be bear by the client.
- 10 All payment shall be paid within 7 days from the date issued of the invoice.
- 11 All increment in cost prior to the commencement of work will be borne by the client. During the agreed schedule of work, any fluctuation of cost shall be borne by RANG DESIGN STUDIO. Any delay of work due to natural and man-made disaster that caused increment in cost will be borne by the client.
- 12 The client should ensure provision of supply on water & power during construction period.
- 13 Upon work completion, notification will be issue to client and if client fails to respond within 7 days, work will be deemed completed and handed over to client.
- 14 Any additional costs due to variation order is required to be settled in full upfront before commencement of work.
- 15 All work performed will be deemed to have been satisfactorily handed over to client if client does not raise any issue within 7 days after hand over.
- 16 Client shall provide site's piping system plan, or else RANG DESIGN STUDIO shall not be responsible for any damages incurred during construction work.
- 17 All 3D visualize drawing proposed by RANG DESIGN STUDIO are for illustration purposes only. Construction work shall follow 2D detail drawing.
- 18 Additional charges of RM 200 - RM 300 / view on 3D visualize drawing shall be applied for the fourth time and onward, subject to the work of amendment.
- 19 All items and dimension are subject to final site measurement and final design proposal.
- 20 RANG DESIGN STUDIO shall not bear any responsibility on any loss and mistakes caused by personnel hired by clients.
- 21 RANG DESIGN STUDIO shall not bear any responsibility to any loss and damage on any personal belonging being left unattended on site .
- 22 Work shall only commence upon acknowledge of payment based on agreed payment term below.
- 23 As the payment terms agreed has been breached, RANG DESIGN STUDIO reserved the rights to stop all in progress and pending work.
- 24 Client should supply tile, light fitting, electrical appliance and etc. material needed in prior to commencement of work.
- 25 Once quotation is confirmed and commencement of work, value of quotation are not allow to be deduct. All changes are only allow to be contra.

Kindly indicate your agreement by signing this quotation and return to RANG DESIGN STUDIO. Validity of 30 days shall begin from date of quotation.

Kindly make payment to :

RANG DESIGN STUDIO  
Public Bank  
3232 9214 19

Agreed By : \_\_\_\_\_  
Name : \_\_\_\_\_  
Date : \_\_\_\_\_

\* Please update the bank slip after payment is done.